Evidence of Performance

Testing of Air Infiltration / Exfiltration, Static Water Penetration, Structural Performance

Test Report No. 19-001989-PR03

(PB-A01-02-en-01)



Kriezi 55

19300 Aspropyrgos

Greece

Product Tripple sliding projecting side-hung casement

2,654 mm x 2,646 mm

Designation System: FMW92

Shipping name: FMW92 THERMO

Material: Aluminium system with thermal break

Performance-relevant

product details Overall dimensions

 $(W \times H)$

Client

Special features

The vapour pressure equalisation of the glazing rebate has to be ensured. Material compatibility must be taken into account. Material durability must be taken into account. The strength, durability and material compatibility of the adhesive system was not part of the test and is tested separately.

Results

	Test performed	Summary of test results	
ASTM E 330	Preload	± 600 Pa	Passed
ASTM E 283	Static air leakage Infiltration / Exfiltration	± 75 Pa ± 300 Pa	Measured values are shown in the protocol
ASTM E 331	Static water penetration	+ 150 Pa	Passed
	Structural performance - Test load 100 % of design wind load, procedure B	± 1,200 Pa	Passed
ASTM E 330 ASTM E1233/E1233M	Structural performance by Cyclic Air Pressure Differential - 100 % of design wind load	± 600 Pa	Passed
	Structural performance - Proof load 150 % of design wind load, procedure A	± 1,800 Pa	Passed

ift Rosenheim 20.12.2019



Testing was conducted on basis of information provided by the customer

ROSENHEIM

Testing in accordance with:

ASTM E 283-04 ASTM E 547-00 ASTM E 331-00 ASTM E 330-02

ASTM E1233/E1233M-14

Representation



Instructions for use

The data and results refer solely to the tested and describes specimen. Classification remains valid as long as the product and the above basis remain unchanged. The results can be extrapolated under the manufacturer's own liability subject to observance of the relevant specifications set out by the applicable product standard. This test/valuation does not allow any statement to be made on any further characteristics regarding performance and quality of the construction presented; in particular the effects of weathering and ageing were not taken into account

Notes on publication

The ift-Guidance Sheet "Conditions and Guidance for the Use of ift Test Documents" applies.

Contents

The report contains a total of 36 pages.

Michael Breckl-Stock Deputy Head of Testing Department **Building Component Testing**

Dimitrios Moustakidis, MSc, Dipl.-Ing. Operating Testing Officer **Building Component Testing**



